SHOWN ON SPCS 27

E 220,000 | E 230,000 | E 240,000 | E 250,000 | E 260,000 | E 270,000

N 740,000 | N 730,000 | N 720,000 | N 710,000

T 5 S. | T 4 S.

T5S R6W. | T5S R5W. | T5S R4W.

NE cor. Sec. 6 T5S, R4W. Fd USGLO BC.

NW cor. Sec. 4 Nothing set

N 728,835.79 E 270,675.74 SHEET 2

NE cor. Sec. 4 T5N, R4W. Fd 1" jack hammer steel bit

NE cor. Sec. 7 T5S, R4W. Fd 2" I.P. USGLO BC.

NE cor. Sec. 9 T5S, R4W. Fd USGLO BC.

NE cor. Sec. 9 T5S, R4W. Fd RR spike

NE cor. Sec. 10 T5S, R5W. Fd USGLO BC.

NW cor. Sec. 18 T5S, R4W. Fd 2" I.P.

NW cor. Sec. 19 T5S, R5W. Fd 3/4" I.P.

NE cor. Sec. 19 T5S, R5W. Fd 2" I.P. set in conc.

NE cor. Sec. 20 T5S, R5W. Fd 1/2" I.P. set in conc.

NE cor. Sec. 17 T5N, R4W. Fd 3" I.P. w/ BC.

Center Sec. 17 T5N, R4W. Fd 2" I.P.

NE cor. Sec. 23 T5S, R5W. Fd 1/2" I.P.

NE cor. Sec. 19 T5S, R4W. Fd Cap, set 2"x2" hub

SW cor. Sec. 19 T5S, R5W. Fd 5/8" rebar

Fd 5/8" bar in mound of pits N 717,933.61 E 227,906.08 SHEET 1

Set 5/8" rebar Set 1/2" I.P.

NE cor. Sec. 25 T5S, R5W. Fd 1" I.P.

Watermelon Rd

SW cor. Sec. 29 Nothing set

SW cor. Sec. 28 Nothing set

SW cor. Sec. 27 Nothing set

NE cor. Sec. 34 T5S, R5W. Fd 1/2" I.P. in conc.

NE cor. Sec. 35 T5S, R5W. Fd I.P. set in conc.

Indian Rd

SE cor. Sec. 31 T5S, R5W. Fd 1/2" pin in HH

SE cor. Sec. 32 T5S, R5W. Fd 4"x4" post

SE cor. Sec. 33 T5S, R5W. Fd 1 1/2" I.P.

NE cor. Sec. 17 T5N, R4W. Fd 3" I.P. w/ BC.

Center Sec. 17

Stoutt

1" = 2000'

0 2000 4000 6000 8000

SCALE 1" = 2000'

LEGEND

- Set 5/8" rebar unless noted otherwise
- Set 1/2" I.P.
- Set copper weld rod

PRELIMINARY

ELLIS, MURPHY, MOGATE AND JOHNSON
CONSULTING CIVIL ENGINEERS
PHOENIX, ARIZONA 1984

U.S. ARMY ENGINEER DISTRICT
LOS ANGELES
CORPS OF ENGINEERS

DESIGNED
DRAWN
CHECKED JCA

BOUNDARY SURVEY
PAINTED ROCK RESERVOIR
GILA BEND, ARIZONA

SUBMITTED BY:
DATE:

CONTRACT NO. DACW09-72-C-6049
DELIVERY ORDER NO. DACW09-72-M-1335

SHEET 4

1-602 309-02

SPCS 27

DIN# 49642-2