GLEC 282-7552 SEDONA
1666 LF NW PERIF
300 LF NW PERIF

N

Scale 1" = 200'

Registered Professional Engineer (Civil)
CERTIFICATE NO. 8699
ROBERT ROLAND JOHNSON
Arizona U.S.A.
8-7-79

NOTE:
ALL DATA RELATIVE TO SECTION LINES & CORNERS NOT FOUND HAS BEEN BASED ON GLO RECORDS OF SURVEY AND HAS BEEN FOUND TO BE RELATIVE TO COLLATERAL EVIDENCE WITHIN ACCEPTABLE LIMITS. THE NORTHERN BOUNDARY IS A RESULT OF RETRACEMENT OF LINES OF AN APS EASEMENT DOCUMENT AND THE RELATIONSHIP OF EXISTING TRANSMISSION TOWERS TO THOSE LINES.

CORNER COMMON TO SECTIONS 12 & 1 T1NR4E AND SECTIONS 7 & 6 T1NR5E. FD. BC IN H.H. IN McKELLIPS ROAD.

SET HUB set 1/2" rebar

125'

33'

NW 1/4 SW 1/4 SEC 7 T1N R5E

APS SURVEY LINE

SET 1/2" REBAR

℄ A.P.S. ROW

N. 61° 46' 01" E Calc. 1530.67' Calc.

SET HUB SET 1/2" rebar

SW 1/4 SW 1/4
SECTION 7
T1NR5E

Area 3581180.90 S.F.
82.213 Acres

1710.91' Calc.
S. 00° - 22' 00" W. Calc.

N. 61° 46' 01" E Calc.
538.30' Calc.

125'

33'

SET HUB SET 1/2" rebar

N. 71° 39' 31" E Calc.
920.73' Calc.

APPARENT TOWNSHIP LINE

N. 01° 08' 00" E. T1NR4E T1NR5E
944.73' Calc.

SET 1/2" rebar

100.00'

SW CORNER SECTION 12.
FD. BC IN HH IN
HAYDEN ROAD.

SET HUB SET 1/2" rebar

SECTION 12
T1NR4E

Area 831980.18 S.F.
19.100 Acres

N02° 10' 50" E
361.54 Calc.

APPARENT SW COR SE 1/4
SE 1/4 SEC 12
SET HUB SET 1/2" rebar

"+" ON TOP OF DRAINAGE HEADWALL

APPARENT CORNER COMMON TO SECTIONS 12 & 13 T1NR4E AND SECTIONS 7 & 18 T1NR5E NOT FOUND. SET HUB set 1/2" rebar

APPARENT SE COR SW 1/4 SW 1/4, SEC. 7
SET HUB SET 1/2" rebar

SE CORNER SEC. 7 NOT FOUND

1343.84' Calc.

1356.96' Calc.

N. 88° 20' 29" W Calc.

254.25'

N 88° 13' 00" W Calc.

BASIS OF BEARINGS

NORTH

E 1/4 COR SEC 13 T1N R4E
W 1/4 COR SEC 18 T1N R5E
FD BC IN H.H. IN PRICE RD.

REVISED: 10-9-79

ASSOCIATED ENGINEERS
Civil Consultants
Phoenix 878-1A Arizona

DIN# 57539-1/1 APLS