MAP SHOWING RESULTS OF SURVEY IN SECTION 11 AND SECTION 12

T. 3N., R. 2E. - G & SRB&M

MARICOPA COUNTY ARIZONA

SURVEYED SEPTEMBER 11, 12 & 13, 1941 FOR

MR. JOHN JACOBS

F.N. HOLMQUIST — ENGINEER

J.O.B. NO. 1780

N

Scale 1 inch = 300 feet

Fences

Corner to Secs 1, 2, 11 & 12 Found Stone

N. 89°-16 E - 2599.4 Sec. Line

ROAD

Fences

N¼ cor. Sec. 12 Found Stone

1250.7 ROAD

N. 87°-11 E - 2501.80

27.934 Sec. Line

NE cor. Sec. 12 Found Stone

Fences

S 62°-35 E 2225.50

3 foot marked ACCO

Set stakes on property Line

Set pipe 33' E & 33' S. of 33' Sec. corner.

33'

Transmission Line

North — Section Line

ROAD

26254

¼ corner Secs 11 & 12 Found Stone

NW¼ Section 12.

Approximate west bank of Cave Creek

Set stakes on this Line

Approximate East Bank of Cave Creek

ROAD

S 0°-25 E - 2640.5

Center Section 11 Set pipe by intersection

S. 89°-35 W - 2628.45 Gross

25.93.45 net

Set stake 33 W. of ¼ corner

Set Stake 33 E. of ¼ corner

N. 88°-24 E.

Center Sec. 12 Set iron pipe by intersection

21.28

N. 88° 24 E.

1250.7

Fence

33'

E¼ cor. Sec. 12 Found Stone

Fence

N. 5 Fence cor. encroaches 7.5 ft. East of property line and encroaches N. 5 Power line encroaches 4.5 ft East of property line

Set stakes on N. Line SE¼ Sec. 12

Found and checked iron pipe

N0°-27 W

1316.6

1318.3

NW¼ SE¼ Section 12

Fence

S0°-04 W 2623.3

Fence

SE¼ Section 11

SW¼ Section 12

Transmission Line

Section Line

ROAD

Property Line

Telephone and power line is approximately 28 ft East and parallel with Section Line

Set iron pipe

Found and checked iron pipe

Found pipe

33'

N. 88°-30 E - 1250.8

N. 0°-26 W

S 0°-25 E - 2640.30

Fence

1320.15

ROAD

5/4 corner Sec. 11 Stone in N. 5 Fence Power line 4.5 ft North, 2.5 ft West of ¼ corner

20'

N. 09°-36 E — 2631.8

Power Line is 2.8 ft. South and parallel with Section Line

Set property stake 33' N. of Sec. Corner (Assumed)

Set property stake 33' E. of Sec. corner

33'

33'

S. 88°-36 W - 2639.74

Set stakes on Sec. Line

Corner to Secs 11, 12, 13 & 14 T. 3 N. R. 2 E. Found stone

Set stakes on this Line

2633.2

1316.6

1318.3

Set 2x2 stake

1250.87

S 88°-36 W - 2501.74

1250.87

SE cor. Sec. 12 Found Stone

¼ corner Sec. 12 Set iron pipe

DWT 5 8091-1