

ADDENDUM NO. 1

June 23, 2004



Title:

**WORK ORDER NO.: 68959, MC85 – Bullard Wash to Litchfield Road
CY 2004-76**

Owner: Maricopa County Department of Transportation

The above contract documents are herein modified. The provisions of said documents applicable to these modifications remain unchanged unless specifically indicated otherwise. This Addendum No. 1 forms a part of the Contract Documents and modifies the provisions as follows:

INVITATION TO BID

The Bid Opening for this project has been changed to Tuesday, June 29, 2004 at 2:00 p.m. Bids will be received by the Maricopa County Department of Transportation, 2901 West Durango Street, Phoenix, Arizona 85009 until 2:00 p.m. (Phoenix time) on the above date and then publicly opened and read at 2901 W. Durango Street, Phoenix, Arizona 85009.

BIDDING SCHEDULE

The existing Bidding Schedule shall be deleted in its entirety and replaced with the Bidding Schedule of Addendum No. 1.

ALL OTHER PROVISIONS SHALL REMAIN IN FULL FORCE AND EFFECT.

A handwritten signature in black ink, appearing to read "Samir Hatab", written over a horizontal line.

Samir Hatab, P.E.
Project Manager

REMINDER: Bidder shall submit this Addendum in its entirety with the complete bid document, and shall acknowledge this Addendum on the second page of the proposal.

MC 85
Bullard Wash to Litchfield Road
WO # 68959
CY 2004-76

Item No	Description	Unit	Quantity	Unit Cost	Total
104.04000	Partnering	Allowance	1	\$5,000.00	\$5,000.00
107.01500	Community Relations	Allowance	1	\$10,000.00	\$10,000.00
107.02000	AZPDES	Lump Sum	1		
110.06000	Mobilization / Demobilization	Lump Sum	1		
111.02000	Type II Engineer's Field Office	Lump Sum	1		
220.10000	Plain Riprap, D50 = 8"	m ²	144		
301.01000	Subgrade Preparation	m ²	90.118		
321.01300	Asphalt Concrete Pavement (Superpave-Heavy) (19mm mix), 6" thick	tonne	25,296.4		
321.01500	Asphalt-Rubber Concrete Pavement, 1.5" thick	tonne	6,324.3		
321.02000	Rideability	Allowance	1	\$36,000.00	\$36,000.00
329.02000	Bituminous Tack Coat (Contingent Item)	tonne	31.07		
340.01110	Vertical Curb & Gutter, MCDOT Std. Det. 2030, H=150mm (6")	m	3,127.00		
340.01151	Single Curb Termination, MAG Std. Det. 222	EACH	6		
340.01155	Concrete Single Curb, MCDOT Std. Det. Std. 2030, H=150mm (6")	m	5,064		
340.01210	Concrete Sidewalk, MAG Std. Det. 230	m	73		
345.01100	Adjust Manhole to Grade, MAG Std. Det. 422	EACH	6		
345.01200	Adjust Water Valve to Grade, MAG Std. Det. 391-1-A	EACH	2		

MC 85
Bullard Wash to Litchfield Road
WO # 68959
CY 2004-76

W.O. No. 68959

Page 12a of 34

Item No	Description	Unit	Quantity	Unit Cost	Total
345.04400	Relocate Manhole	EACH	1		
350.01000	Removal of Existing Improvements	Lump Sum	1		
350.01300	Removal of Existing Signs	Lump Sum	1		
350.01800	Remove of Existing Concrete Curb and Gutter	m	552		
350.01850	Remove of Existing Concrete Single Curb	m	661.5		
350.01900	Remove of Existing Sidewalk	m ²	122		
401.01000	Traffic Control	Lump Sum	1		
401.01100	Uniformed Off-Duty Officer	Allowance	1	\$10,000.00	\$10,000.00
405.01000	Survey Markers, MAG Std. Det. 120-2, Type "D"	EACH	6		
415.01100	Guardrail, MCDOT Std. 2036, Type A and 2039, G4(2W)	m	151		
415.02000	Guardrail Terminal (ET-2000 LET)	EACH	2		
461.01600	Paint Median Island	EACH	13		
462.01100	100 mm (4") White Thermoplastic Traffic Stripe	m	11,693		
462.01200	100 mm (4") Yellow Thermoplastic Traffic Stripe	m	6,591		
462.01510	Thermoplastic Pavement Arrow	EACH	13		
463.01100	Reflectorized Raised Pavement Marker (Type D, Yellow 2-Way)	EACH	341		
463.01200	Reflectorized Raised Pavement Marker (Type G, Clear, 1-Way)	EACH	1,240		

Item No	Description	Unit	Quantity	Unit Cost	Total
464.02000	Perforated Sign Post	m	115.90		
464.02001	Perforated Sign Post Foundation, MCDOT Dtl. 2058	EACH	41		
465.01001	Flat Sheet Aluminum Sign Panel, Engineering Grade	m ²	5.70		
465.01002	Flat Sheet Aluminum Sign Panel, High Intensity Grade	m ²	23.22		
465.01003	Flat Sheet Aluminum Sign Panel, Diamond Grade	m ²	2.74		
471.60047	No. 7 Pull Box	EACH	4		
471.61112	Sch 40 PVC Electrical Conduit, 75mm (3") w/ #8 Bare Copper Wire	m	252		
471.61412	Sch 40 PVC Electrical Conduit, 100mm (4") w/ #8 Bare Copper Wire	m	3250		
481.00057	No. 7 Fiber Optic Pull Box w/ Extension	EACH	18		
481.40425	Sch 40 PVC Electrical Conduit, 100mm w/ 4-25mm (4-1"), 2500# Mule Tape	m	3250		
505.06248	Concrete Scupper, MAG Std. Det. 206, Curb opening = 1.2m (4')	EACH	5		
505.06296	Concrete Scupper, MAG Std. Det. 206, Curb opening = 2.6m (8'-6")	EACH	21		
505.10110	Catch Basin, MAG Std. Det. 531, Type "B"	EACH	2		
523.01118	Headwall, MAG Det. 501-1 & 2, Straight Type (Modified), for 450mm (18") pipe	EACH	4		
523.01718	Headwall, MAG Det. 501-1 & 2, 'L' Type (Modified), for 450mm (18") pipe	EACH	1		
523.11118	Headwall, MAG Det. 501-1 & 2, Straight Type (Single), for 450mm (18") pipe	EACH	3		
523.11124	Headwall, MAG Det. 501-1 & 2, Straight Type (Single), for 600 mm (24") pipe	EACH	6		

Item No	Description	Unit	Quantity	Unit Cost	Total
610.08500	Relocate Existing Fire Hydrant	EACH	2		
618.02318	450 mm (18") RGRCP, Class III	m	143.5		
618.02324	600 mm (24") RGRCP, Class III	m	74.4		
TOTAL BID AMOUNT IN WRITTEN NUMBERS:					
TOTAL BID AMOUNT IN WRITTEN WORDS:					
SUBMITTING CONTRACTOR'S NAME:					